

CLAWS - T3B Technology for SuperKEKB



Calorimeter for ILC



CALICE Collaboration Meeting
Munich
September 2015



Introduction

1. Upgrade to SuperKEKB Accelerator and Belle II Experiment



2. Commissioning of the SuperKEKB Accelerator



For Beam Diagnostics:

- Phase I (without Belle II)
- Phase II (with Belle II, but no VXD)
- Phase III (full detector)


3. Scintillation Light And Waveform Sensors (CLAWS)



- Different small detectors in Phase I&II
- **Fast system** with capability of sampling over **extend times**
→ CALICE Technology in SuperKEKB commissioning

4. Timeline and Outlook

Phase I: Goals



Bunch Scheme:

- Bunch spacing of 4 ns
- Circulation time of 10 μ s
- Two injection bunches per 2500 bunches
- Two injection bunches 100 ns apart

Goals of Phase 1:

- Decay time of noise from injection bunches
 - ▷ Sample over extended times
- Measure exact trigger delay
 - ▷ Fast timing
- Verify timing structure in KEKB
 - ▷ Fast timing

The Problems:


No idea what background to expect + System needs to be ready yesterday

Phase I: Hardware




Narrow timing in Phase I calls for hardware basically ready to go:

- ▷ System based on T3B Technology



T3B Sensors & Boards:

- MPPC 50 Silicon PMs from Hamamatsu as sensors
- $30 \times 30 \text{ mm}^2$ Scintillators
- Integrated pre amp
- Wrapped in reflective foil
- Dynamic range up to 15 MIPs



Distance of 37m between IP and hut (Scopes):


- Additional amplification stage (Mini circuits ZF-L 500)



Phase I: Hardware



11 T3B Boards at hand, each with slightly different amplitude:



The Idea:

- Identify two Groups of 4 boards each (Similar gain for same voltage, $\pm 10\%$)
- One V_{bias} - line per group
- Per Board/Channel:
 - 3m coax cable
 - ZF-I 500 Amplifier (located near boards)
 - 45 m BNC (Signal)
 - 45 m Supply voltage ($V_{bias} + V_{pre\ amp}$, 4 wires, TP, shielded)
- Distribute voltages to cables with common box

45 m BNC-Signal



45 m PreAmp+Bias Volt.




45 m Amp Voltage



Voltage Distribution



Phase I: Hardware



Keysight 6700B Modular Powersupply:

- 2 Low Volt. modules ($V_{Amps} + V_{Pre Amps}$ up to 20 V)
- 2 High Volt. modules (V_{bias} up to 100 V)
- Rack mountable
- Operated via Labview

Readout out for CLAWS Phase I:

- Picked up updated version of T3B solution
 - ▷ Picotech picoscope 6404D
- 8 bit resolution
- 5 Gs/s (1.25 Gs/s per channel)
- 2 GS Ultra deep memory
- Up to 400 ms of one continuous waveform
- Labview integration possible (under study)

Hardware safely arrived at KEK:

- 0.5 Kg of SiPM boards
- 60 Kg of cables
- Total of 110 Kg were shipped to Japan

Phase I: Installation



Beam Abort diamonds
total ionizing dose


CsI Crystals(pure) EM particles

BGO Crystals:
EM particles/dose

64x Pin Diodes:
X-ray & ionizing dose

He-3 tubes:
Thermal neutron rate

Micro TPC:
fast neutrons rate and recoil spectrum



Phase I: Installation



Beam Abort diamonds
total ionizing dose

CsI Crystals(pure) EM particles


CLAWS (sCintillation Light And Waveform Sensors)

BGO Crystals:
EM particles/dose

64x Pin Diodes:
X-ray & ionizing dose

Micro TPC:
fast neutrons rate and recoil spectrum

He-3 tubes:
Thermal neutron rate




Phase I: Installation






Beam Abort diamonds
total ionizing dose

CsI Crystals(pure) EM particles

CLAWS (sCintillation Light And Waveform Sensors)



Phase II: Hardware



Sensors arranged in two PCB boards in *PXD* location with 8 SiPM-tile combinations each (~ 31 mm from *IP*):

- 20 x 20 x 3 mm³ scintillator tiles with Mainz dimple wrapped in reflective foil
- New low noise SMD SiPMs (LCT4/5 with trenches)
 - 50 µm pixels
 - 1 mm² active area ~ 20 keV/photon
 - ▷ for ~ 5 keV SR photons go for 3x3 mm²
- SiPMs directly mounted on PCB
- Pre amps, LV and HV supply and micro-coax signal cables all integrated in PCB
- ~ 2 W per ladder
- Maybe integration of LED calibration system

Timeline and Outlook



CALICE Technology is part of Belle II commissioning experiment at SuperKEKB:

- **Phase I:**

- In spite of time constraints, find system with fast timing + sampling over extended times - T3B technology based on SiPM and scintillators
- Transport setup to KEK - arrived
- Installing of CLAWS - scheduled for third week of September
- Get working DAQ - to do, but on good way
- Begin taking data - February 2016

- **Phase II:**


- Finalize hardware design - to do
- Order and build hardware - several parts already at hand/to do
- Extend DAQ to phase II - to do
- Install and take data - end of 2016/beginning of 2017




Backup

Backup

SiPM Characteristics




Phase II Mechanics



Borrowed from C. Kiesling



Problem: Injection Noise



Total rate: 50 Hz

20 % deadtime for PXD


Principle:

continuous injection, developed by KEKB machine physicists

Liouville theorem:

bunches cannot be injected into same phase space volume

- > „cooling“ by synchrotron radiation
- > particle loss -> „noisy bunches“



C. Kiesling, Project Review 2011, MPI, Dec. 19-20, 2011

28