


# SVD assembly and plan

Katsuro Nakamura

Sep. 7, 2015


VXD mechanics meeting

# Flow of SVD assembly




- Endring CO2 pipe brazing
- Endring/endflange gluing
- Outer cover gluing
- Ladder mount

# SVD endring CO2 pipe brazing




# Background


- We would like to glue the end ring to the CFRP cones before the B2GM in February 2016 and start the preparation of the ladder mount. The brazing of CO<sub>2</sub> tubes to the end rings should be finished earlier.
- I like to assign 3 months for the brazing and examination after the production
- We need to finish contract at beginning of October.
- We started discussion with Welcon.



# Test brazing in March 2015

- They made test pieces by using an hydrogen brazing oven.
  - A copper based brazing solder (JIS Z3262).
  - Process temperature:  $\sim 1100$  °C.
- 3 samples were produced
  - Two channels are made with 3 mm separation.
  - The  $\varnothing 1.7$  mm tube from DESY is used.
  - passed the flow test, leak test and pressure test successfully.






- **The continuous hydrogen brazing oven used by Welcon.**

<http://www.tokyobraze.co.jp/device/>

[http://www.tokyobraze.co.jp/wp-content/uploads/2013/06/2009\\_St.pdf](http://www.tokyobraze.co.jp/wp-content/uploads/2013/06/2009_St.pdf)


# Remaining issues

- In the spring test, they used short tubes. We are interested in how stably the tubes are set to the end ring before brazing.
  - If tube are loose, brazing solder can overflow.
- **Brazing of the miniature VCR connector to the tube.**
  - Put a nut of VCR connector on the pipe in advance?




# Brazing test pieces

The end ring design




- Additional step in the brazing hole structure: which might prevent overflow of the solder to tubes, inspired by the discussion with Carsten in June and Kohriki san in August.
- Final endrings has  $\Phi 1.65$  holes for the pipe insertion. We can enlarge them as we want.

The test piece used in test 2015 spring




Proposed hole shape: The added step might prevents solder overflow






# Readiness of VCR connector


- **8 half VCR connectors are necessary for the final Endring brazing.**
  - 2 half VCR connectors/ FWD or BWD half structure
- **Which male or female nuts should we put on Endrings?**
- **When are these VCR connectors available?**




# SVD support structure assembly



Endring + Endflange




Outer cover



# Status


## Endring gluing:

- **1<sup>st</sup> trial of Endring gluing has been done for both FWD/BWD**
  - with 1<sup>st</sup> half of FWD/BWD mockup Endring
  - STYCAST 2850FT + Catalyst23LV
- **Several issues were found from the 1<sup>st</sup> trial. Remedies for them were applied on jigs. They are now in production.**
  - Better jig flatness
  - Controlled alignment with linear bushings
- **2<sup>nd</sup> trial of Endring gluing will be done after the production of the modified jigs finishes.**
  - FWD: the middle of Oct. or the begin of Nov.
  - BWD: the middle of Dec.





## Outer cover gluing:


- **1<sup>st</sup> trial of outer cover gluing has been done.**
  - Araldite2015
- **2<sup>nd</sup> trial of outer cover gluing will be done after reproduction of the FWD-BWD support rod.**
  - The end of Nov.



# Outer cover gluing




lack of adhesive





- **We had an exercise of outer cover gluing.**
  - Araldite2015
  - we found control of glue mount is an issue for the gluing.

# Required components

- **Phase-3**
  - Endring
  - Endflange
  - CFRP outer cover
  
- **Phase-2/DESY beam test**
  - SVD cartridge
    - no Endring and no CFRP cone
  - Endflange (phase-2 design)
  - CFRP outer cover (phase-2 design)
  
- **Schedule of DESY beam test**
  - March or April, 2016
  
- **By the beam test, SVD cartridge preparation, and phase-2 outer cover assembly have to be finished.**



Phase-3 SVD support structure  
(Endring + Endflange)



# Schedule of SVD structure assembly (2015)

- **Sep. 2015**
  - CMM measurement for the assembled 1<sup>st</sup> half FWD-BWD mockup Endring
    - The gluing was done at
  - SVD cartridge: finalize design and start production
  - Wire-cut for FWD-Endring-gluing jig
- **Oct. 2015**
  - Practice of Endring gluing (2<sup>nd</sup> half FWD mockup Endring)
  - Phase-3 Endring: CMM measurement
  - (Start preparation of BWD Endring gluing jigs)
  - 22<sup>nd</sup> B2GM
- **Nov. 2015**
  - Reproduction of FWD-BWD support rod
  - **Phase-2/beam test outer cover gluing**
    - or with another practice
    - finalize the method
  - Wire-cut for BWD-Endring-gluing jig
- **Dec. 2015**
  - Practice of Endring gluing (2<sup>nd</sup> half BWD mockup Endring)
    - finalize the assembly method

# Schedule of SVD structure assembly (2016)

- **Jan. 2016**
  - CMM measurement for the assembled FWD-BWD mockup Endring
- **Feb. 2016**
  - 23<sup>rd</sup> B2GM
  - **FWD/BWD phase-3 Endring gluing**
- **Mar. 2016**
  - CMM measurement for the assembled FWD-BWD phase-3 Endring
  - Delivery of phase-2 SVD structure to DESY
  - DESY beam test?
- **Apr. 2016**
  - DESY beam test?
- **May. 2016**
  - **Phase-3 outer cover gluing**
- **Jun. 2016**
  - 24<sup>th</sup> B2GM



# Schedule of SVD structure assembly

2015	Sep.		↕ Finalize SVD cartridge design and start production
	Oct.	22 <sup>nd</sup> B2GM	↕ 2 <sup>nd</sup> trial of Endring gluing (2 <sup>nd</sup> half FWD mockup Endring)
	Nov.		↕ <b>2<sup>nd</sup> trial of outer cover gluing (beam test)</b>
	Dec.		↕ 2 <sup>nd</sup> trial of Endring gluing (2 <sup>nd</sup> half BWD mockup Endring)
2016	Jan.		↕ CMM measurement for the glued FWD-BWD mockup Endring
	Feb.	23 <sup>rd</sup> B2GM	↕ <b>Endring gluing (FWD/BWD phase-3 Endring)</b>
	Mar.	↕ DESY beam test	↕ CMM measurement for the glued FWD-BWD phase-3 Endring
	Apr.		↕ <b>3<sup>rd</sup> trial of outer cover gluing (phase-2)</b>
	May.		↕ <b>Outer cover gluing (phase-3)</b>
	Jun.	24 <sup>th</sup> B2GM	




# CO2 cooling on SVD cartridge (phase-2)

- We'd like to use Swagelok connectors.
  - fix them on SVD cartridge
- Does they match to connectors on IBelle/Marco?



Fix connectors around here


Glands



Short Tube Butt Weld


Tube Size	Nominal Wall Thickness	VCR Size in.	Ordering Number	Dimensions			Working Pressure		
				A	C	E	Ni	SS	Cu
Dimensions, in. (mm)							psig (bar)		
1/8	0.028	1/8	6LV-2-VCR-3S-2TB7 <sup>Ⓟ</sup>	1.08 (27.4)	0.75 (19.1)	0.06 (1.5)	8500 (585)	8500 (585)	6800 (468)
		1/4	6LV-4-VCR-3S-2TB7	1.10 (27.9)			5100 (351)	5100 (351)	5100 (351)

Blind (Undrilled) Gland



VCR Size	Ordering Number	A
Dimensions, in. (mm)		
1/8	SS-2-VCR-3-BL <sup>Ⓟ</sup>	0.70 (17.8)

# Ladder mount



# Task list

- **Ladder mount jig: Sato-san**
  - after B2GM
- **Keratherm attachment jig: Sato-san**
  - prototype: the middle of Oct.
- **Set-screw fixation tool: Florian**
  - prototype is already developed
- **CO2 cooling pipe bending: Florian**
- **CO2 cooling pipe attachment: Fillipo and Florian**
- **Cabling/piping during ladder mount: Katsuro and Suzuki-san**
- **Collision test with Class-C ladders**
  - Oct. 27 at Tsukuba B1

# Necessary days for Layer 3 mounting

- **Ladder mounting: 1.5 days/ladder**
  - including EQA test (noise & calibration measurement) and coordinate measurement
  - Left half: 3 ladders
  - Right half: 4 ladders
- **Thermal test: 1.5 days/half-layer**

# Necessary days for Layer 4, 5, and 6 mounting

- **Ladder mounting: 1.5 days/ladder**
  - including EQA test (noise & calibration measurement) and coordinate measurement
  - Layer 4: 5 ladders/half-layer
  - Layer 5: 6 ladders/half-layer
  - Layer 6: 8 ladders/half-layer
- **Keratherm attachment + ORIGAMI cooling pipe attachment: 1.5 day/half-layer**
- **Thermal test: 1.5 days/half-layer**

# Others

- **Outer cover attachment + Transportation of half-structure from the mount table to a strage:**
  - 1 day/half-structure

# Total

- **1<sup>st</sup> Layer 3: 6.0 days**
- **1<sup>st</sup> Layer 4: 10.5 days**
- **1<sup>st</sup> Layer 5: 12.0 days**
- **1<sup>st</sup> Layer 6: 15.0 days**
- **Half-layer detachment: 1 day**
- **2<sup>nd</sup> Layer 3: 7.5 days**
- **2<sup>nd</sup> Layer 4: 10.5 days**
- **2<sup>nd</sup> Layer 5: 12.0 days**
- **2<sup>nd</sup> Layer 6: 15.0 days**
- **Half-layer detachment: 1 day**
  
- **Total: 90.5 working days ~ 5 months**

# Assembly Schedule

based on Tanaka-san's slide  
on VXD meeting

- We have to share the VXD assembly table for assemblies of two VXD systems
  - VXD for phase-2 and BEAST
  - VXD for physics run (phase-3)

