

- Plans with pilot run modules

	W30	W35	W36
IF	3 <sup>a</sup>	2a <sup>b</sup>	2a <sup>b</sup>
OF1	0	2a <sup>b</sup>	2a <sup>b</sup>
OF2	2a <sup>b</sup>	2a <sup>b</sup>	2a <sup>b</sup>
OB1	2 <sup>c</sup>	2b <sup>e</sup>	4 <sup>f</sup>
OB2	2 <sup>d</sup>	4 <sup>f</sup>	2 <sup>c</sup>
IB	2a <sup>b</sup>	4 <sup>f</sup>	2a <sup>b</sup>

0: no faults  
 1: pixel level faults  
 2a: row level faults  
 2b: column\* level fault  
 3: high impact faults  
 4: lethal faults  
 5: to be clarified

\* Column level faults in AI2 can be repaired by rework (grade 2b → 0).

Status after AI, including poly testing

Assignment of the modules:

- W30-OB1, W35-OB1, W36-OB2 → assembly with prototype ASICs, kapton interconn.



- W30-OF1, W35-OF2 → assembly with prototype ASICs, PCB interconn.

- W30-IB and W35-IF → L1 ladder for test beam and Beast

- W35-OF1 and W35-OB1 → L2 ladder for Beast test beam and Beast






## ● PXD9-6 – the PXD Pilot Production

- 3/30 "hot" wafers (W30, W35, W36)
  - still a lot of process control, tests, and measurements "on the fly"
  - started Oct 2014 → 1<sup>st</sup> wafer finished July 2015
  - lot of lessons phase III learned!! (Phase III in its full beauty was never done before)
  
- status today:
  - W30 finished, cut, modules assembled ....
  - W35 was held back for detailed measurements and Cu on W36 had to be repeated
  - W35 & W36: Cu e-p finished, seed layer removal today ...
  - ATG – Passivation – cut litho – cutting: ~3 more weeks



# ● Flip-Chip

- :- 4 modules from W30 sent to IZM
  - :- took about three weeks (holiday season)
  - :- OF1, OB1, OB2 → no issues
  - :- OF2: placement was done manual FC machine, reflow in the same oven
  - :- errors during placement, last two SWB misplaced
  - :- rework at IZM possible





# ● SMD


:- OF1, OB1, OB2 finished

:- no SMD on OF2

:- small issue on OF1: "side balls" because of slightly too much solder paste



● SMD



## ● Next steps

### : - Kapton attachment

- : - first dummy-dummy done
- : - needs some improvement of the jigging (kapton bending tool)
- : - repeat tests
- : - assembly of OB process dummy (partial ASICs, full SMD)
- : - ... the real thing ... OB1 And OB2

### : - testing:

- : - new design by Christian Koffmane under way (submitted??)
- : - breakout board pre-test?
- : - cooling plate for base jig???
- : - 1<sup>st</sup> sanity check of ASICs
- : - deep breath → power-on matrix → "first light" → switch off → open bottle

Very little time left: pretty important to have Cd spectrum for BPAC!!