

DHH

Igor Konorov

TUM Physics Department E18

10-th VXD workshop
September 14-16 2016
Santander

Overview:

- Irradiation test of GLENAIR transmitters
- GLENAIR transmitters and magnetic field
- Status of optical components orders
- Display Port
- Plans

- 2015 irradiation campaign

- Glenair 050-301

- 850 nm, 2 Gbps


- Power consumption 300mW/channel

- Size 20x10x10 mm

- Neutron : $2.5 \cdot 10^{12}$

- Gamma : 230 kRad

TX (with blue stripe)




- 2016 irradiation campaign

- Glenair 050-363

- Only Gamma irradiation



Setup Diagram




1. Aurora Simplex Protocol

- 125Mhz reference clock
- 2 Gbps with 8b10b encoding
- Continuous data stream

2. Error detection

- Soft error counter (protocol level)
 - 1) Corrupted data is not valid in 8b/10b table
 - 2) Corrupted data is in the table but has the disparity error
- Data error counter by checking data content
:if received \neq expected then cnt = cnt++



1. Data read and write via IPBus

Rx

The screenshot displays two control interfaces for PXD:H1035 and PXD:H1036. The top interface (PXD:H1035) shows RX status with a table of RX0-RX3 parameters. The bottom interface (PXD:H1036) shows TX status with a table of TX0-TX3 parameters. Both interfaces include buttons for 'GTX Reset' and 'Long RST', and display various system metrics like temperature and voltage.

PXD:H1035 RX Status:

	RXEQMIX	EYE	UP	Hard Err	Soft Err	Frame Err	Data Err	Data Check
RX0	0	31	<input checked="" type="checkbox"/>	0x0	0x1B	0x0	0x0	<input checked="" type="checkbox"/>
RX1	0	23	<input checked="" type="checkbox"/>	0x0	0x1A	0x0	0x0	<input checked="" type="checkbox"/>
RX2	0	23	<input checked="" type="checkbox"/>	0x0	0x1D	0x0	0x0	<input checked="" type="checkbox"/>
RX3	0	20	<input checked="" type="checkbox"/>	0x0	0x18	0x0	0x0	<input checked="" type="checkbox"/>

PXD:H1036 TX Status:

	Seed(2 bytes)	Next Seed	UP	Data Ger
TX0	0xABCD	0xD5E6	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
TX1	0xABCD	0xD5E6	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
TX2	0xABCD	0xD5E6	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
TX3	0xABCD	0xD5E6	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>

Tx

2. Error information is recorded in the file by a script

- Gammacell rate
Rate = 6,5 Gy/min = 655 Rad/min
⇒ Exposure time = 380 min or 250kRad

Results:

- 4 channels were exposed simultaneously
- Device worked stably, not a single error detected
- Slight change of power consumption below 1%



Remaining questions about optical transmitter

Yutaka question : do we have enough safety margin?

To answer direct measurement has to be performed at Belle in 2017

Radiation monitor:

CERN developed radiation monitor which can be considered for such measurements. No for free.

Should we discuss it next time?

Kovar


- Used for the sub-mounts in laser and photodiode hermetic TO packages
- Matches thermal expansion coefficient with glass which seals laser
- Electro-magnetic properties do not play a role for device operation
- Transmitter functionality has been tested @0.5T
- It's planned to test @1.2T

Problem of magnetic forces to be investigated

- Dock Box coordinates
 - FW z 1645÷2060 mm; r 300÷403 mm
 - BW z -995÷-1410 mm; r 344÷446 mm
- More probably there is no field map in this region
- In contact with Yasushi Arimoto
- To perform measurement is advisable
- Forces on Transmitter along PCB, Transmitter screwed to PCB but still forces may propagate to connector
- Reinforcement to keep transmitter at place needed !!!

I. B_r Component

A. B_r component on z-x plane.



Status of Optical Components

- 20 Transmitters delivered + 25 ordered
- All optical LSHF cables ordered , delivered this year

Display Port Cable

Single cable for everything:


- TRG/GCLK
- JTAG
- Current source
- DHP sense voltages VSS, VDD
- Power for optical transmitter

1. Display Port Cable 9mm


- Diameter: 9mm
 - Length: 15 meter
 - High speed link between EMCM and DHH
- **Correct DHPT command through**

2. Display Port Cable 7mm

- Diameter: 7 mm
 - Length: 20 meter
 - **NO** high speed link between EMCM and DHH
- **DHPT command ??**



- 7mm DP cable
HP link → *No, Reflections.*
- 9mm DP cable
HP link → *Yes, Reflections.*




- A, B are transition cards between Infiniband, RJ45 and DP connectors
- Measure Point 1: input of the DP cable
- Measure Point 2: output of the DP cable
- Measure Point 3: input of the EMCM

Observation 1 : input impedance 200 Ohm instead of 100 Ohm
due to alu wire resistance on EMCM


DP Output


EMCM in

9



7





- Because of reflections, 200 Ohm resistor is in parallel
→ *links **can not** be established even with 9mm DP cable*

Observation 2 : DC level of TRG/CLK signals at 50-80 mV

**After introducing 800 mV biasing links can be established with both cables,
with and wo 200 Ohm =>**

Most probable reason for synchronization problems in April

Display Port Cable

Powering of optical Transmitter

- No sense wires
- 7mm cable voltage drop 1.9 V
- 9mm cable voltage drop 0.5 V => reliable powering conditions

Proposal:

Employ 9 mm Display Port Cable

Availability:

15 m LSHF DP cables of 9 mm diameter from a shelf

Required length : 30 cables of 15 m and 10 cables of 17 m

Tests:


- EMCM with optical cables and 20m DP cable – done;
- PXD9 with short(2m) and long(15 m) Infiniband cable to co – in preparation ;
- New B2TT firmware version 0.46, in April DHH was running with 0.46 firmware while SVD worked with 0.45 - done;

Readiness for DESY:

- Start with April setup to confirm synch problem – ready;
- B2TT event number mismatch – tested;
- Switch to UCF (single fiber interface DHC-DHE) - being tested now
- Firmware handling overlapping triggers – next to be tested
- Remapping, waiting for VHDL code from Giessen
- RTM and ATCA CC for optical interface – prototype to be available in November (critical)

Remarks about Planning

Updated PXD Production Schedule



C. Kiesling, BPAC VXD Review, KEK, Oct. 24-26, 2015

12

Milestones for Planning

1. 5 final(!) detectors + 5xDHE + 1xDHC + 1ONSEN – tests and debugging – 6 month
2. 20 detectors + 24xDHE + 4 x ONSSEN – 3 month
3. Complete PXD detector – 3 month

THANK YOU