

#### LMU München - Excellence Cluster Universe

### **PS & Services**

#### **Stefan Rummel**

10<sup>h</sup> VXD Workshop 14.09.16-16.09.16 Santander





#### **Overview**




- Main Production
- Services
- Kapton development



#### **PS Main Production**



- PS is a modular design consisting out of 12 different modules
  - MCU-Card Steering
  - 5 flavors of regulator cards
  - 2 DC/DC converter cards with Step-Down converter
  - OVP card
  - Front- and Back card for interconnections and external interfaces





### **Main production**



- Main production aims for 70 units 20 for KEK-PF and 50 for PXD operation
- All parts for 20 units available including HV cards and precision monitoring for CCG's
- Cards are configured and a basic functionality test has been performed





## Main production – Regulator cards



- Unipolar cards full set, 140 boards available and pre tested
- Bipolar cards full set available, configured, 40 pre tested







## Main production – Regulator cards



#### HV – Card's & CCG Channels:

- Received new feature request just before Christmas
- Monitoring with 20nA resolution for various channels (CCG's, Bulk, HV, Drift)
- → New circuitry for measurement necessary
- Cards have been delivered in early August
- New features are tested successfully
- → Configuration and pre- testing done





### Main production – DC/DC converter cards



- PCB design has been finalized
- Additional feature:
  - Voltage supervisor as additional safety measure
  - Failure at DC/DC converter level can be mitigated before it has impact on output voltages
- First batch available
- 15 tested and commissioned
- Stepdown converter configured to our needs for operation with long cables





### Main production – MCU Card



- Bugs from previous designs fixed
  - MCU watchdog
  - Various smaller issues which where fixed with wires
- Design finished, PCB's available
- First batch of 20 ready
- 15 are successfully commissioned





## Main production – Commissioning



- Assembly of units under way
  - Upload of firmware to MCU
  - Sanity check of full box (current consumption, control, monitoring system...)
  - Calibration
  - Check of calibration
  - Full power test with load
- 6 in queue
- 4 available
- 20 till end of Sept.







### PS operation – Crate controller



- PS are operated in crates offering power, interlocks and individual reset connections
- Piggy back card to control individual PS has been developed
  - Switch on/off inc. fans
  - Reset
  - Current monitoring
- Control software in under development












### **Services**




#### **Kapton**



- Baseline for Kapton production: Kaupke
  - Superior bond strength / surface quality
  - Pricing
  - Easy communication
- 4 x 5 sets ordered and delivered in August
- Offer to purchase further batch from overproduction
- Tests ongoing at MPI bonding, impedance
- → First Kaptons for module assembly available







#### **Power Cable**



- Significant quality issues at previous cable production
- New vendor has been identified
- Throughout quality control using:
  - Visual inspection
  - Electric testing
  - Documentation
- Better internal organization of production process: "Die erforderlichen Parameter, z. B. Abmantel- und Abisolierlängen werden in unseren Arbeitspapieren hinterlegt. Bei der Erst- bzw. Musterfertigung werden diese Parameter an die Rohmaterialien, z. B.
- Sub-D-Leisten, Hauben, angepasst und festgeschrieben."
- Two batches of cables have been produced since July and cross checked
  - Rework of previous production
  - 4 pairs with 14m, another batch in in work








## **Power Cable integration**



- Power cable routing has been finalized
- Worst case length including some safety length of 40cm/ 100cm is 14.5m
- Connecting the longest cables in the first row of the rack will allow to go for 14m





# **Power Cable integration**



PXD - cable lenght for power								date:	28.07.2016	oversize cable lenght
lenght is rounded to	Α	В	C	D	E	F	safety lenght	cable	total	by
100 mm	(outside+KLM)	(unorganized)	(slot area)	(CDCwall-DR)	(dock area)	(DR-plug)	(cable reserve)	(quantity)	lenght	14.500
H-fwd	11100	600	1000	1200	0	200	400	10	14.500	4.000
45°-fwd	8100	500	1000	1600	0	200	1000	10	12.400	31.000
V (I)-fwd	8000	500	1000	1800	1700	200	1000	10	14.200	13.000
V (II)-fwd	8000	500	1000	2100	0	200	1000	10	12.800	27.000
H-bwd	10000	600	1100	900	0	200	1000	10	13.800	17.000
45°-bwd	7500	800	1100	900	1500	200	1000	10	13.000	25.000
V (I)-bwd	7000	500	1100	900	700	200	1000	10	11.400	41.000
V (II)-bwd	7000	500	1100	1000	0	200	1000	10	10.800	47.000
								cable ste	ock in oversize area	205,000



#### **Cable Quality Control**




- Possibility to check cables/services (PP) after handling, installation
- Test for open, short, resistance
- Test cases:
  - PP harness: Samtec MicroDsub, RJ45, Infiniband
  - Power cables
- Cable Tester has been purchased
  - Easy to use
  - Checks assignment, resistance, isolation
- Individual connector harness to test power cables has been produced
- Harness / adapter card for PP's is under way





### **Cable Quality Control**









#### **PP**



- Latest PP with single connector has been designed
- PCB is available
- Necessary cables Glenair, Infiniband, CAT6 available
- Delivery of 4 units within this week








#### **Dock Box**



- Mechanical interfaces finalized
  - "thick" DP cable incorporated
- Crosscheck with Igor / Charlie done
- New feature display port cable
  - No additional cables for power of transmitter
- PCB and components available
- Assembly ongoing, first batch within September





#### **Summary**



- First PS units from Main production available
- Set of final length power cables available for MPI / DESY
- Dockbox, PP's available soon
- Test setup for in house cable testing available





### **Backup**