CLAWS

Fast Scintillators for Injection Background Monitoring in BEAST II Phase II



Miroslav Gabriel Max-Planck-Institute for Physics

> VXD Belle II Workshop Santander

Scintillation Light And Waveform Sensors (CLAWS)

Goals of CLAWS in Phase II:

- Measurement of background time dependence in PXD region
 - Decay behaviour from injection bunches relative to normal bunches
- Change in injection conditions: Phase I vs Phase II
- Evolution over several BXs & many turns
 - Requires sampling over extended times - up to multiple *ms*





Background averaged over 3 channels and multiple injections (phase I)



Sensors

Two Sensor Ladders - 8 Channels Each:

- Mechanical support entirely by PCB
- Channel composition:
 - Scintillating tile: 20x20x3 mm³ BC-408
 - SiPM: MPPC S13360 1325PE
 - PreAmp: 20 dB ~ factor 10

New High-Gain/Low-Gain Settings:

 Bypass PreAmp - switchable from remote O(1 min)

Power Consumption:

- Major power consumer: PreAmps ~ 40 mA
 @ 5 V (rest negligible)
- Total: ~2 W / ladder



SiPMs: Temperature & Noise Rate

Sensors



Hamamatsu MPPC-S13360-1325PE SiPMs:

- Active area 1.3x1.3 mm²
- Large dynamic range 2668 Pixel

Sensor Noise:

- 1 photon event noise rate < 100 kHz
- 4 photon event noise rate < 1 Hz
- Expected MIP response: ~15 photons
- Cut on 4 photons basically no noise
 Impact of Temperature Change:
- Higher noise rate: **no issue**



SiPMs: Temperature & Amplitude



Dock Box



Dock Box Design:

- Box in box: aluminium box coated with capton inside Dock Box electrically isolated
- 16 Amplifiers inside box: 1 per channel ~ 20 dB amplification
- Minor cable patching

Power Consumption:

- 16 Amps: 80 mA @ 15 V
- Total: 20 W peak consumption

Scope & PSU

4 Picoscope 6404D Oscilloscopes for Signal Digitization

(2 from phase I, 2 new):

- 4 full channels + ext. trigger / scope
- 8 bit vertical resolution
- 5 Gs/s (1.25 Gs/s per channel) sampling rate fast timing
- 2 GS Ultra deep memory extended sampling
- 50 ms "waveform" successfully taken in phase I
- Control & Readout via USB 3.0 4 oscilloscopes connected to DAQ workstation
- Only 2 scopes available at DESY test beam

Keysight N6700 PSU:

- 4 channels: 1xVPreAmp, 1xVAmps, 1xVBiasLadder1, 1xVBiasLadder2
- Reused from Phase I no problems encountered
- Control & Readout via DAQ workstation





CLAWS Phase II Workstation & DAQ:

- Same workstation as in phase I possible ram and storage upgrade
- DAQ: Modification of phase I DAQ based on LabVIEW extended to 4 scopes
- Communication with other systems via Experimental Physics and Industrial Control System (EPICS)

Triggering & Timestamping:

- Trigger via external signal connected to ext. trigger of each scope
- Phase I: Timestamp via common Beast time server accurate to ~ 10 ms
- CLAWS trigger in phase II is a remaining an issue!



DAQ

Cabling & Rack Space

Cables - Ladder to Dock Box:

- Signal micro-coax: made from Peek, 2 m (?), outer diameter = 1mm
- V_{Bias} : shielded Twisted Pair, 2 m (?) , outer diameter 3.5mm
- V_{PreAmp}: shielded same

Cables - Dock Box to Electronic Hut:

- 16x RG174: 30m, like RG174 but LSZH, outer diameter = 2.6 mm
- 3xTP: 30m, 2x8 cores, outer diameter = 15mm
- 2xTP: 30m 2x2 cores, outer diameter = 8mm

All cables will be LSZH!

Rack Space:

- Workstation: rack mountable 1U
- PSU: rack mountable 1U
- 4x scopes: on top of workstation, 3-4 U







Calibration & Analysis

1 Pixel noise signal - 1 photon equivalent



Channel wise reconstruction:

 Iterative subtraction on raw waveform yields total amplitude & timing

Dedicated calibration runs every ~ 30 minutes:

- 1 photon events from noise
- 1000 events / channel: O(2 mins)
- Extract average 1 photon waveform for each channel



Hardware Status

Sensor Ladders:

- PCB: manufactured and delivered
- · SiMPs + Elect. Parts: delivered
- Scintillators: manufacturing ready until mid October
- First board ready by end of this week begin commissioning next week

Cables:

- Dock Box to E-Hut:
 - LSZH signal cables order: delivery this week
 - Signal cables for DESY: ready
 - Power cables: partially ready/ being manufactured
- Sensors to Dock Box:
 - Mini-coax: cable at the institute SMA connectors minor issue
 - Power cables: searching for supplier in contact with several suppliers

Dock Box:

- Amplifiers: delivered
- Box, connectors & inside patch panels: being designed focus hardware efforts



Summary & Outlook



Unixtime [s]

Hardware:

- Hardware processing well
- Almost all cables at hand/ awaiting delivery
- Hardware focus on finalising design inside Dock Box & commissioning

Triggering & Timestamping:

 \cdot Open issue

Backup

Silicon Photomultipliers: Temperature Stability

Sensors



Hamamatsu MPPC-S13360-1325PE SiPMs:

- Active area 1.3x1.3 mm²
- Dramatically reduced noise :
 - 1 photon event < 100 kHz
 - 4 photon event at the same time < 1 Hz
- Substantially larger dynamic range (2668 Pixel)
- Overall very good uniformity of gain of detectors when operated with same bias voltage



Beast II



Silicon Photomultipliers & Scintillating Tiles

Sensors





Hamamatsu MPPC-S13360-1325PE SiPMs:

- Active area 1.3x1.3 mm², 2668 pixel
- Ultra low noise rate (1 photon rate < 100 kHz, 4 photon rate < 1 Hz)
 Polystyrene Scintillator Tiles:
- 30x30x3 mm³ + half sphere
- Radiation hardness > 1MRad
- ~18 photons/MIP (⁹⁰Sr & cosmic tests)

Pre-Amplifier :

Closest possible mounting to SiPM (improved S/N)

SuperKEKb LER Commissioning: First Signals



~ 200 ns

Feb 1st:

Begin of LER commissioning with linac tests

Feb 8th:

- 08:00 AM first positron injections into LER
- <u>03:30 PM first coincidental signals in two</u>
 <u>CLAWS sensors</u>

First Particles at the IP of SuperKEKb!

SuperKEKb LER Commissioning: First Turns



Feb 1st:

Begin of LER commissioning with linac

Feb 8th:

08:00 AM first positron injections into LER 03:30 PM first coincidental signals in two

CLAWS sensors

Plot 0 📈

Plot 1

Plot 2 Plot 3

Feb 9th:

- 05:20 PM First turns can ٠ be seen in SuperKEKb
- 05:30 4 Turns •
- End of the day more than • 50 have been reached