High Energy Accelerator Research Organization

9/14/16



Experience with the open CO2 system @ KEK Katsuro Nakamura

Sep. 14, 2016 10th VXD workshop

10th VXD Workshop

KEK

Open CO2 system

- Open CO2 cooling system developed by HEPHY
- O(100W) cooling power
- Li-CO2 is supplied by bottles outside.
- Automatic control of the CO2 flow rate is implemented. But not CO2 temperature (= CO2 pressure) currently.
- Naoya Kambara (Tokyo University of Science) is studying the system at KEK.



System Flow Diagram



9/14/16

CO2 cooling system setup at KEK B1



- From 1 CO2 bottle, about 20kg CO2 is available for the CO2 system
 - (actual amount of CO2 inside the bottle is 30kg).
- Currently, once one CO2 bottle gets empty, we have to switch off the CO2 cooling system, connect to another bottle, and then restart the CO2 system.
- In future, we will implement switching valves, which enable us continuous switching the bottles without stop of the system.

Requirements on the open CO2 system

- Role of the open CO2 system
 - Cooling test during SVD ladder mount. (highest priority)
 - Test thermal conductance between endmounts/bridges and Endrings.
 - Test thermal conductance between ORIGAMI cooling pipes and APV25 chips (through Keratherms).
 - Test SVD ladder performance under the cooling down (secondary priority)
 - Mechanical deformation study under the cooling
 - DESY is also performing this study with dummy ladders, but check it with a real ladder (class-C) is preferable.
 - Possibly, study of S/N ratio improvement (Maybe w/ class-B- ladder).

Requirements

- 100W cooling capability
 - Total power dissipation from ORIGAMI APV25s in half L6 ladders (the largest unit in the cooling test): 8[ladders] x 30[APV25s/ladder] x 0.4[W/APV25] = 96[W]
- Stabilities in temperature and CO2 flow control
- Reasonable CO2 gas consumption
- Reasonable test time

Stability of Flow Rate (Deviations in Flow Rate)



Cooling Capability Test (Setup)

- Voltage supply applies a load on the test pipe directly.
 - Pipe: SUS304, OD: 1.6mm, ID: 1.4mm
 - Voltage supply: max. 20V, max. 20A (max. 400W)
- The resistance of the pipe limit the power up to about 260W.
- Monitor pipe temperature with a sensor on the pipe.



KEK (High Energy Accelerator Research Organization)

Cooling Capability Test (Results)



Resulting pipe temperatures

flow rate [g/s]	pipe temp. [°C] w/o load	pipe temp. [°C] w/ 100W load
2.2	-1716	-76
3.0	-54	10 11
4.0	-76	6 7

- We tested flow rates of 4 g/s, 3 g/s, and 2.2 g/s under a heat load of 100W.
- In any flow rates, there are no difference in T1 and T2.
 - \rightarrow Still cooling power was remaining after the heat load.
- But pipe temperatures become lower for higher mass flow.

Comparison the results with before shipment



- Results in 2.2 g/s shows good consistency with Lukas's measurement and a enough cooling power for 100W load.
- But, Results in 3 g/s and 4 g/s are higher temperature than Lukas's measurement and our 2.2 g/s result.
 - They looks inconsistent with our 2.2 g/s result.

Reasons of the inconsistency



We saw large drift in the pipe temperatures during CO2 system operation.

- The CO2 temperature is getting higher during the operation. About 10 degrees difference was observed between the beginning and later.
- 2.2g/s measurement: done earlier, 3.0g/s, 4.0g/s measurement: done later
- \rightarrow Need to control the CO2 temperature T1 (= pressure P1) as well as the flow rate.

Also thermal isolation form is not tightly surrounded on the pipe.

- \rightarrow We will improve the the form attachment.

Control of CO2 Temperature

Drift in CO2 temperature (= pressure) during operation

- Because the current system doesn't control CO2 temperature, the temperature changes during operation.
- We have to be very careful for the temperature drift, otherwise we loose reproducibility of the cooling test results.
- If the system gets stabilized and we don't change the valve settings, the temperature seems stable. But, the system stabilization takes about 1000s (about 17min.) and consumes 4 kg CO2 in 4 g/s flow rate.
- And in the current automatic mode, the stabilized temperature is about -10 degrees, but not less than that.
 - Do we need to use -20 degrees?
 - Preferable, because it is worth to check mechanical performance of ladders under -20 degrees or lower with the open CO2 system.
 - In this case, a solution for -20 degrees is manual-mode operation, but stability is not guaranteed.
 - Even turning on heat load can change the CO2 temperature in manual mode.
- Can we control the CO2 temperature?

CO2 Temperature Control Scheme



Flow rates in MV1-MV2 map



Pressure in MV1-MV2 map



Solution for CO2 temperature control

In manual mode, we can control the CO2 temperature.

- The first valve (MV1) controls flow rate.
- The second valve (MV2) controls pressure (= temperature).
- However, this manual operation doesn't have good stability.
 - We have to keep checking the temperature monitor to adjust the valve frequently, especially in the beginning of operation.
 - Even if we apply heat load, this changes the temperature and we need to change the valve setting again.

Ideally, temperature control in automatic mode is rather preferable and useful

- as well as we are controlling flow rate.
- But, maybe, need more development time...

Time and CO2 consumption

CO2 consumption until the temperature gets stabilized:

- 2.0 g/s: 14 kg
- 3.0 g/s: 6 kg
- 4.0 g/s: 4 kg
- Larger flow rate looks better to minimize the CO2 consumption until the stabilization.
- In the current automatic mode, if we change the flow rate after the stabilization, the temperature gets unstable again.
 - Change from 4.0 g/s to 2.0 g/s after the stabilization to save CO2 is not good option due to this phenomena.
- So far, keep running in automatic mode of 4.0 g/s flow rate is the best operation considering the test time and CO2 consumption.

flow rate [g/s]	time [s]	CO2 consumption [kg]
1.0		(more than 5kg)
2.0	7000	14
3.0	2000	6
4.0	1000	4

cf. 20kg CO2 are available from 1 bottle.

Future open CO2 system setup in clean room





- All the cooling pipes will be laid on the floor in order to prevent dew drop from the roof.
- FWD and BWD cooling lines are selected on the open CO2 system side.
- All the necessary parts are under quotation now. They will be set up by the end of Oct.

Safety interlock system

We had a small accident:

- CO2 system was turned off while the heater to the dummy load was kept on.
- Fortunately, before smoke or fire, we notice it with a bad smell from the load.
- The same accident happened when Lukas tested the system.

Possible solutions:

- Interlock signal from the temperature sensor on the load.
 - We will implement it soon.
- Interlock signal from the open CO2 system
 - Currently, there is no such output from the system, which indicates whether the system is running properly or not.
 - It is good that the system has such output for safety purpose, and this makes the system simple.

Summary

- Cooling capability
 - Even flow rate of 2.2 g/s shows excellent cooling performance.

Stability in automatic-mode operation.

- Flow rate: excellent stability
- Temperature: At least needs 17min. and 4 kg CO2 until the stabilization. Moreover, we cannot achieve -20 degrees.
 - Temperature control as well as flow rate control would be preferable.

Flow rate during the test

- 4.0 g/s seems the best considering the test time and CO2 consumption.
- System setup in B1
 - Now ongoing. Setup will finish by the end of Oct.
- Interlock system
 - We will implement an interlock system based on temperature sensors.



CO2 phase diagramf



9/14/16



9/14/16

10th VXD Workshop