

LMU München - Excellence Cluster Universe

Services and Grounding

Stefan Rummel

21.02.17






- Dockbox
- PP
- Kapton
- Grounding scheme




- Two independent functionalities:
 - Adapter between power connectors and common mode filter
 - Fan-out of dig. signals and optical transmission
- Prototypes with transmitter and DP cable available
- Mechanics cross-checked with Karlheinz
 - Outline - ok
 - Thickness near 2mm! – next batch fine
- Circuitry around transmitter
 - Similar to the test board from Igor
 - Transmitter is working
- RJ45 connector pin assignment issue in footprint
 - to be addressed in next production
- Infiniband connector was apparently tilted while reflow:
 - All pads in the first row (drainwires) were soldered, signal row was elevated limited yield
 - EMS immediately offered to rework them, next batch delivered in 2 weeks





- Docks incorporate capacitors for common mode filtering
 - Current value 100nF – $Z < 1 \text{ Ohm}$: 2MHz-80MHz
 - Going for higher C?
- Transmitter with modules operated for the first time @ DESY
 - One link shows instability, reason unclear

→ Mass production can start after robust module operation is demonstrated




- PCB's:
 - Individual E-Test
 - Impedance control
 - “Test-coupon” on each batch can be made available
- Manufacturing:
 - Visual inspection, AOI

Lab Testing:

Except of the transmitter the Dockbox is a fan-out which serves as an adapter between different cables

- Cable tester can be used to check electrical connections between relevant nodes
- Successfully used for the rework of the existing boards
- Testing link quality in some test setup






- 8 PP prototypes without housing are in use in the collaboration
 - Test showed an issue with the assignment of the RJ45 cable
 - Issue was traced back to footprint of connector in Dockbox – exchange of two pairs
 - Two links exchanged
 - Fixed on documentation
 - Current strain-relief is not sufficient to prevent pairs in the InfiniBand cable from moving
 - Infiniband particular critical since it uses solid wires, stiff bundled pairs
 - Peel off of pads for Inifinibandcable
- Additional measures required:
- (1) potting and/or removing cable jacket seem to be most straight forward and compatible with existing mechanics
 - (2) Thinner wires in Inifiniband cables (AWG 26 or 28) → impact on signal quality?
 - (2) Through hole contacts for InfiniBand → Implemented in next batch, deeper cutouts on PP base already foreseen
- Locking mechanism, guide posts where in discussion



- DHH – needs a set (4) of analog signals for operation and defining local ground:
 - DCD_Mon
 - Signals to detect DHP power state
- New baseline:
 - DCD_MON comes with DGND_SENSE as reference – Currents in DCD_MON?
 - DHP_IO_SENSE and DGND_SENSE to detect power state (prev. DHP_IO and local PP DGND)
- Both optical transmitter in Docks and DHH are referenced to module DGND using the sense wire
- This scheme is implemented in the PP PCB's currently produced





- First hoods and bases made of Aluminum will be available from MPI
 - Appropriate for single connector interface
 - PP PCBs with TH – delivery scheduled for next week
 - Assembly will take around 3 weeks
- First PP prototypes with current state of mechanics available
- Main question: Are the TH contacts sufficient, does bending directly after PP harm them?



- PCB's standard measures: E-Test, Impedance
- Manufacturing has several manual non standard steps; take care of:
 - Stripping of insulation on data lines
 - Staying within the allowed volume
 - Assignment...
- PP contains no active circuitry
- Full test of assignment, open/shorts, resistance sufficient to check the electric properties
- Test can be done using the cable tester @ LMU
- Link quality to assess signal integrity



- Production ongoing
- We have to make a decision on the size of the various capacitors....
 - Input from Gated-mode testing?



- **Baseline are the recommendations from Fernando**
- Deviations from this occurred on the PP side where shields of the data cables where connected to PP via the crimp
- Measures to insulate the braid from the housing must be implemented
- A set of issues came up regarding the referencing of the transmitter circuitry and DHH with respect to the module
 - New baseline is to put DHH and Transmitterground on the same potential as the module DGND using the respective sense wire
 - Flexible handling of Drainwire connection on Dockbox level – capacitor implemented – so can be left open or AC coupled



Backup