



VXD Environmental Monitors and Interlock

Lorenzo Vitale

BPAC focused VXD review

KEK, October 17, 2017

Outline

- Radiation: sCVD Diamond sensors
- Temperature: NTC and FOS
- Humidity: Dew Point “sniffers”
- VXD Local Hardwired Interlock (VLHI): PLC

Prototypes have already been operated in Phase 1 or VXD Beam Tests

- here more on installation status and schedule
- both Phase 2 and Phase 3 sometimes overlapping


Environmental monitoring summary

Subsystem	Phase 1/Beam Test Sensors	Phase 2 Sensors	Phase 3 Sensors
Time span	Feb-Jun 2016/Mar 2016 + Mar 2017	Feb-Jun 2018	Dec 2018 →
Diamonds	4	8	20
NTC	26	26	56+12
FOS	1 fiber 8 sensors	4+2 fibers 26 sensors	38+2 232 sensors
Dew Point	1	1+3	1+3





RADIATION: SCVD DIAMONDS

sCVD Radiation Sensors: Phases 2 and 3



6 + 6 sensors
close to SVD L3
support rings

4 + 4 sensors
PXD-beam pipe



Now:

Installing

Assembling + test,

→ calibration 1-2 weeks/sensor

Phase 2: 8 "PXD" sCVD sensors



Phase 3: 8 "PXD" + 12 "SVD"

In parallel !


Phase 1 results




Integrated dose



integrated dose measured in the four position on the beam pipe



Phase 1 diamonds– aborts, refilling




Dia0
 Dia1
 Dia2
 Dia3

↑
 HER
 Abort

↑ ↑ ↑
 3 LER
 Aborts

HER current, pressure
 LER current, pressure

Correlations with LER, HER



FW_180, BW_0: very sensitive to LER, not to HER

FW_0, BW_180: same sensitivity for both

HER current, pressure


LER current, pressure

Dia0
Dia1
Dia2
Dia3

sCVD sensors: assembly, tests, calibration

- **Package preparation:**

HV test, sensor gluing, cables soldering/gluing,
I-V in the dark



- **Transient Current Test (TCT) with alpha source**

fast amplifier + fast oscilloscope

sCVD crystal quality, electrons/holes transport parameters

- **Beta source (3 MBq):**


Priming/pumping to fill-in traps

Stability tests at “high” current (about 1 nA)

Calibrations: current vs particle flux (realized by changing the source distance), comparison with Fluka simulation and film dosimeters


Examples from 17 tested sensors - 1

I-V measurements with β source of 4 sensors:
sCVD crystals are not all equal; asymmetric behaviour




Examples from 17 tested sensors - 2

Priming/stability studies with β source at different HV values:
example from one sensor




Examples from 17 tested sensors - 3

Stability at about 1 nA may depend (not always) on HV polarity





Examples from 17 tested sensors - 4

Calibrations: extracted from the sCVD current vs source distance, at different HV value and polarity, compared with FLUKA simulations
New: also radiochromic film dosimeters, collaboration with Naples




Dose range: 3 kGy- 100 kGy





Phase 3: Diamond installation

6 final diamond sensors
mounted in June 2017
on the first 2 SVD half-cones (BW and FW)





Phase 2: Diamonds installation

- All 8 diamonds for phase 2 installed on the beam pipe on Sept 18-19 (4 days before scheduled)
- Functionally tested with a ^{90}Sr beta source
- Two radiochromic films were attached on their inner surface
- Moreover two thin strips on BP



Diamonds readout electronics

- **Prototype 4-channel module:**
 - HV, currents digitization and averaging, beam abort logics
 - successfully tested in Phase 1**
- **Final engineered version in delivery now**
 - the FINAL re-engineered hardware parts of the radiation monitoring electronics (FPGA board, analog front-end board, HV modules, Ethernet interfaces) are **READY AND TESTED**
 - The mechanical assembly of 2 modules for 8 diamonds are ongoing for Phase 2
 - 3 additional modules + 1 spare will be ready for Phase 3 (ordering now)
- **Development in collaboration**
 - Elettra Sincrotrone Trieste scpa (G.Cautero et al.)





TEMPERATURE: NTC AND FOS

SVD Temperature

- Requirements:

Temperature monitoring & interlocks:



0.1°C precision, 1°C accuracy

Monitoring points:


- close to SVD FE chips (heat sources)
- Inlets and outlets of CO₂ cooling pipes & half rings (possible indication of cooling failure)

- Design:


- FBG (Fiber Bragg Grating) sensors on optical fibers (FOS), embedded in SVD ladders (Airex)
- NTC thermistors, with hardware interlock capability, on cooling pipes and half-rings



NTC final configuration for Phase 3



NTC read out for Phase 3



NTC temperature sensors: installation

- Phase 3


In June the read out system and all the sensors were shipped to KEK, and re-tested: they have be mounted (1/2) at the end of **July** and (1/2) in **December** for the Ladder Mount of the two SVD halves

- Phase 2

In July the back-up read out system and the sensors used for the DESY beam tests were dis-assembled and shipped from DESY to KEK. It has re-assembled in **September** with small modifications for Phase 2

Temperature FOS sensors: first half 2017

- Calibrations of 55 fibers completed
- Cutting fiber excess & glueing clamps
- System test with splitters and first prototype of EPICS software
- Mechanical tests in May at KEK:
 - insertions on all ladders
 - interference with Layer 6
 - logistics in B1
 - glueing on the SVD Outer Cover



FOS Schedule

Schedule:

- 2 Fibers for phase 2 outer cover installed on May
- 2 Fibers for phase 3 outer cover → installed in September
- 3 Fibers for phase 2 cartridge → installed in September
- 19 fibers SVD Ladder Mount +X half → first installed on Layer 4 Sep-Oct
- 19 fibers SVD Ladder Mount -X half → to be installed starting from January 2018

Present status:



- 2 readout “interrogators” are available at KEK
- All fibers are available at KEK



HUMIDITY: DEW POINT SNIFFERS

Dew Point Sniffers: overview

- Based on Dew Point Sniffers
- Reduced system (1 line)
 - Successfully operated in in two Beam Tests at DESY
- Full system: completely defined
 - 4 Vaisala Dew Point Transmitters
 - Pressure sensors
 - Bronkhorst flow meter
 - Calibration system (DewGen, DewMaster)
 - 2 pumps




Dew Point Sniffers: status


- Mechanics:
 - CAD design completed
 - Mechanical components available
 - Mechanical assembly: started beginning of October
- Sensors, electronics:
 - All components available, **except 4 pressure sensors (delayed delivery)**
 - Readout interfaces and drivers: ready
 - Linux software developed & tested for all sensors/actuators
- Next:
 - Completion of mechanical assembly and tests before shipping to KEK in November
 - EPICS interface in October
 - “DESY prototype” to be delivered at KEK as back-up

Dew Point Sniffers: mechanics

- Crate hosting Vaisala sensors, pressure sensors, flowmeters, and electronics
- CAD design completed, components available (except 4 pressure sensors)
- Mechanical assembly started



Dew Point Sniffers: sensors & readout



Sensors:
readout, linux software
developed and tested: OK

Next: EPICS interface


Dew Point Sniffers: sensors & readout



Vaisala Dew Point
Transmitters
& readout board



Bronkhorst
Flowmeters
& readout board



Pressure sensors
readout board




VXD LOCAL HARDWIRED INTERLOCK (VLHI): PLC

VLHI Overview

- Vertex Local Hardwired Interlock (VLHI) is hardwired PLC-based system aimed at prevention of damage to VXD
- It interlocks VXD PS basing on hardwired inputs and variables from EPICS, and also it is supervised by EPICS

- Documentation:
[confluence page](#)
[Belle II internal note](#)



VLHI simulator describing its logics [running online](#)

VLHI Interlocks Status

- PLC hardware:
 - I/O completely defined (modules, cables, connectors) (see spreadsheet and CAD schematics in backup)
 - PLC crate interconnections, power lines: CAD design completed
 - PLC crate mechanics, patch panel: ready (see photo)
 - PLC crate cabling: almost done
- Next:
 - PLC crate cabling, to be finalized in October
 - Functional tests in Trieste with simulated inputs, outputs programmed with the agreed interlock logics, before shipping to KEK for installation in E-hut in December

VLHI crate: back view

Back view of the PLC crate: patch panel, all I/O connections defined





CONCLUSIONS AND SCHEDULE

In Summary


- Radiation: sCVD diamond sensors**

BEAST Phase 1 analysis, NIM paper
 Assembly & calibration of sensors in Trieste

now 17 completed, 8 ongoing, out of 4+8+20

Final electronics in preparation for Phase 2,
 Detector installations completed for Ph1 & Ph2

*4 Ph1, 6 SVD Jun17, 8 Ph2 Sep17, 6 SVD Dec17, 8 ph3
 early 2018*





- Temperature: NTC and FOS sensors**

All NTC+FOS sensors and electronics tested &
 calibrated in Trieste

Installation at KEK ongoing



From May 2017 to Apr 2018



- Humidity: Dew Point “sniffers”**

Design and test of components completed,
 assembly in progress in Trieste

Shipping in Nov, inst/test Dec





- VXD Local Hardwired Interlock (VLHI)**

Design and simulations completed

PLC & I/O assembled, cabling in progress

Shipping in Nov, inst/test Dec



VXD monitoring: schedules @ KEK

Commissioning at DESY/KEK - summary Item	2016												2017												2018											
	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12					
SuperKEKB Phase 2	[Red bar]																																			
SuperKEKB Phase 3	[Red bar]																																			
DESY beam test, BEAST Phase 2 assembly	[Green bar]																																			
BEAST Phase 2 installation at KEK	[Green bar]																																			
SVD Ladder Mount	[Green bar]																																			
PXD ready/delivery to KEK	[Green bar]																																			
VXD integration, commissioning & installation	[Green bar]																																			
Commissioning at DESY/KEK - summary																																				
Phase 2 cables installation	Radiation												BW												FW											
Phase 2 - 8 sCVD sensors installation & commissioning	[Orange bar]																																			
Phase 2 Rad.Mon.installation & commissioning - KEK	[Orange bar]																																			
Phase 2+3 Rad.Mon.signals from/to SuperKEKB, cabling	[Orange bar]																																			
Phase 2+3 Rad.Mon.signals from/to SuperKEKB, tests	[Orange bar]																																			
Phase 3 cables	[Orange bar]																																			
Phase 3 - 12 sCVD sensors (SVD) installation	[Orange bar]																																			
Phase 3 - 8 sCVD sensors (PXD) installation	[Orange bar]																																			
Phase 3 - final Rad.Mon. commissioning	[Orange bar]																																			
Phase 2 - (few NTC sensors substitution) DESY	[Blue bar]																																			
Phase 2 NTC cables installation	[Orange bar]																																			
phase 2 FOS sensors in layers 4,5,6, etc, tests	[Orange bar]																																			
phase 2 fibres from DOCKS to E-hut	[Orange bar]																																			
phase 3 FOS sensors in layers 4, 5, 6, etc, insertion & tests	[Orange bar]																																			
phase 3 fibres from DOCKS to E-hut	[Orange bar]																																			
phase 3 final FOS commissioning	[Orange bar]																																			
Sniffers delivery at KEK	[Orange bar]																																			
Sniffers piping to E-hut (DESY crew) at KEK	[Orange bar]																																			
Sniffers final commissioning at KEK	[Orange bar]																																			
Sniffer: on SVD ladder mount: prototype? No	[Orange bar]																																			
Interlock cabling and tests at KEK	[Orange bar]																																			
Interlock final commissioning at KEK	[Orange bar]																																			

Phase 2

Phase 3

Lab activities at INFN Trieste
Installation and commissioning at DESY or KEK




Backup



RADIATION: PHASE 1 STUDIES

Diamonds: Abort Buffer Memories

Present configuration of revolving Abort Buffer Memories to be improved with really “running sums”




Buffer Memories: Snapshot Example

Example of snapshot of Buffer Memories (Mem1 to Mem4) for Dia3 = BW_0 in stable beam conditions, with average $I(\text{BW}_0) = 1.5 \text{ nA}$


Noise decreases with increased averaging, from about 0.47 nA to $< 0.04 \text{ nA}$

OK both for fast ($10 \mu\text{s}$) and slow ($> 1 \text{ s}$) beam aborts with appropriate thresholds

100000 entries
1 s history
 $\sigma = 0.47 \text{ nA}$




BW_0 Mem2




1000 entries
1 s history
 $\sigma = 0.18 \text{ nA}$

1000 entries
50 s history
 $\sigma = 0.047 \text{ nA}$



BW_0 Mem4



100 entries
100 s history
 $\sigma = 0.034 \text{ nA}$

Diamonds in BEAST 1: Summary

- Main goals for BEAST 1 and results

- Validation of sCVD sensor choice, mechanics, cables **OK**
- Characterization of prototype electronics **OK**
- Stability and reliability of operation over several months **OK**
- Correlations with accelerator conditions and backgrounds, contributions to BEAST studies **OK**
- Initial studies of beam abort features **just started**
- Integration in EPICS **marginal trick now: to be done!**

- Plans for the future

- Check absolute calibrations of the 4 BEAST-1 sensors
- Mounting, test, calibrations of final diamond sensors in Trieste
- Final electronics production (at least 2 boxes ready for BEAST – 2)
- Prepare for BEAST – 2 and SVD installation



RADIOCHROMIC FILMS DOSIMETRY (WITH NAPLES)

Absolute dose measurement with radiochromic films in BEAST II phase 2 (Napoli group)


- Non-invasive radio-chromic films has been proposed for integrated measurements during phase 2, **collaboration with Trieste group**
- Proposal well accepted by Japanese colleagues
- Study of dose radial dependence
- Independent dose measurement cross-check for several sub-detectors
- Thin layer films and easy handling: negligible material budget
- High spatial resolution, no processing required to develop or fix the image, insensitive to visible light

Film types proposed for BEAST application

- B3 (3kGy-100 kGy), to be positioned very close to interaction point
- HDV2 (10 Gy – 1kGy) for intermediate range
- EBT3 (1-60 Gy) calorimeter region
- Wide range of doses could be covered with the 3 film types proposed

B3 films


- Plastic polyvinyl butyral by Riso laboratory Denmark
- Thickness: 20 μm
- Dose range (3kGy-100 kGy)
- Readout peak at 554 nm



Absorption spectrum of Riso B3 dosimeter film

HD-V2

- Active layer (12 μm) coated on a 97 μm polyester substrate
- Dose range (10Gy-1kGy)
- Readout peak maximum at 670 nm



Strips on FANGS


Film positioning for Beast II phase 2

- Films on diamond radiation monitors
- Strips at several positions along z on the SVD cartridge
- Wrapping around Titanium part of beam pipe
- Long strips along the three FANGS support structures
- On the PLUME ladder
- Films on ECL: positioning under discussion
- Other positions: dock spaces to monitor dose on electronics,....


Schedule

- Films procurement in progress
- Installation will start in September 2017
- Films calibration on several radiation fields and energies (2018)
- Removal of films at the end of Phase II run
- Dose results from film analysis (November 2018)


Film positioning in Phase 2



Diamonds



Films on PLUME detector



Small pieces on Beam pipe




Strips on FANGS




RADIATION: SIMULATION RESULTS

PXD: Ph2 vs Ph3 dose rate

Phase 2



Phase 3





SVD: Ph3 dose rate

Dose


(a) Campaign 16

(b) Campaign 15



dose [Gy/smy] by background and SVD layer

BHWide	123	50	32	21
BHWide_LA	18	5	4	2
Coulomb_HER	9	2	1	1
Coulomb_LER	63	24	21	12
RBB	73	28	16	12
Touschek_HER	0	0	1	0
Touschek_LER	122	31	15	11
twoPhoton	531	82	51	34
	3	4	5	6





SVD: Ph3 vs Ph2 dose rate

Dose

(a) Phase3

(b) Phase2



dose [Gy/smy] by background and SVD layer

BHWide	123	50	32	21
BHWide_LA	18	5	4	2
Coulomb_HER	9	2	1	1
Coulomb_LER	63	24	21	12
RBB	73	28	16	12
Touschek_HER	0	0	1	0
Touschek_LER	122	31	15	11
twoPhoton	531	82	51	34
	3	4	5	6


dose [Gy/smy] by background and SVD layer

BHWide	6	2	1	1
BHWide_LA	1	0	0	0
Coulomb_HER	0	0	0	0
Coulomb_LER	34	6	4	3
RBB	0	0	0	0
Touschek_HER	0	0	0	0
Touschek_LER	140	45	22	9
twoPhoton	10	4	2	2
	3	4	5	6




CO₂ cooling system: NTC sensors

Temperatures of the half rings
and at the inlets and outlets
of each CO₂ circuit



+ 8 sensors to cross-check
a sample of FOS sensors
+ 12 for CO₂ in the external circuits,
requested by the CO₂ group

NTC final locations and fixing




12 sensor pairs attached to the 12 half-rings supporting the SVD ladders:

4mm alignment holes in half rings L5 and L6, glued L3-4

16 sensor pairs on the inlets and outlets of the CO₂ cooling pipes:
on the “streuli connectors” of CO₂ inlets-outlets

A few (~8) positioned near fibers for cross-calibration


NTC Sensors in SVD Cartridge @BT



Similar to the final SVD configuration, where pairs of NTCs will monitor inlets and outlets of the CO₂ cooling lines, and each of the supporting “half rings”, with their cooling channels

NTC Temperature @BT

The temperature of the CO₂ cooling system (MARCO) decreased gradually in steps. With MARCO running at -27°C, NTC readings of SVD CO₂ in/out lines were at -20°C






FBG Sensors Calibrations

- Fiber Bragg Grating (FBG)

Maximum reflectivity at $\lambda_B = 2n_{eff}\Lambda$

Wavelength λ_B depends on strain ϵ ,
temperature T

$$\Delta\lambda_B = \lambda_B(1 - \rho_\alpha)\Delta\epsilon + \lambda_B(\alpha + \xi)\Delta T$$




- Calibrations

Environmental chamber

Reference PT100

Polynomial fit (3rd order)

Stable and reproducible
results, within specs.




FOS state

- All the FOS fibers have been shipped to KEK
- Both read-out modules have been shipped to KEK
 - One installed in B1 for ladder mount
 - One in the E-hut for Phase 2 (and Phase 3), F2 rack
 - Not really feasible to have another readout
- Splitters in the E-hut too, F2 rack
- Cabling in the SVD ladder mount area in B1 done in Sept. 11-15 allows to monitor 9 fibers.
- Cabling for phase 2: 14 patch cords (6SVD+8PXD) almost done
BWD (Sept. 25-27) to be completed Oct. 12-16
- Testing software running on the elog laptop
- EPICS software: Szymon prepared and tested a first version in July-August also with splitters. Needs more testing and final implementation

Phase3: FOS on SVD outer covers

FOS fibers with 4 sensors were glued and tested on the SVD outer covers in Sept (Phase 2 were done on May)



Phase 3 activities: ladder-mount

First 2 FOS on L4+x, locations 4.09, 4.10; unfortunately L4.006 in 4.10 was dismantled on Sept 26, the other later

- In location 4.09 with a modified “dedicated” clamp and “after” H shape
- In location 4.10 with a “normal” clamp and “before” H shape





TEMPERATURE IN PXD: IN DCP

Temperature in PXD-1



Module Temperatures


- measured via DHP temperature diode
- all covers, with clamp, chiller @ 18°C
 - only DHPs powered
 - 25-30
 - DHPs and DCD powered, but DCD analog OFF
 - 30-35
- > for both W37_OF1 and EMCM
 - DHPs and DCDs powered and DCD analog ON
 - 50-58
 - all powered (DCDs analog ON and matrix)
 - 55-60
- calibration?
 - even with only DHPs powered: 5-10 spread between DHP temperatures

Temperature in PXD-2





Temperature Interlock

- Utility IOC can monitor the DHP temperatures and trigger an emergency shutdown
- Utility IOC is a temporary solution for lab setups and will not be used in the final experiment
- Heartbeat between PS Seq IOC and DHH IOC required for a stable and save solution
 - This requires some work on both IOCs, to produce/receive the heartbeat and perform the temperature measurement



Humidity calibration system




Dew point generator (DewGen) for calibrations

Humidity: inputs from Dew Point Sensors




DMT242 Compact Dewpoint Transmitter for Desiccant Dryers

Vaisala DMT242B
Dew Point Transmitters
[-60, +60]^oC dew point range




Prototype system under construction




Simplified Block Diagram, PLC

VXD Local Hardwired Interlock = VLHI



Schneider Electric Modicon M340
+ BMX DDM 16022 Discrete I/O
+ BMX AMI 0410 Analog Input



VLHI I/O spreadsheet

VLHI PLC crate configuration: inputs, outputs, connectors (preliminary, August 24, 2017)


Unit	purpose	I/O channels	type	assignment	PLC memory	cable				PLC Pannel Connector		Reference person	Institution				
						type	length	from	to	type	pins						
CPS3500	power unit																
BMX P34 20302	M340 CPU		USB														
			Ethernet														
			CANopen														
BMX DDI 1602	16-ch digital input	%I0.1.0	EBOOL	Manual	%MW001	?											
slot 1		%I0.1.1	EBOOL	Beam Abort	%MW002	?											
		%I0.1.2	EBOOL		%MW003												
		%I0.1.3	EBOOL	from Central Interlock Sol_Abn	%MW011							Sadaharo Uehara	KEK				
		%I0.1.4	EBOOL	from Central Interlock Env_Mon	%MW012							Sadaharo Uehara	KEK				
		%I0.1.5	EBOOL	from Central Interlock WaterLeak	%MW013							Sadaharo Uehara	KEK				
		%I0.1.6	EBOOL	from Central Interlock EH_Power	%MW014							Sadaharo Uehara	KEK				
		%I0.1.7	EBOOL	CO2 ER COND. (DSS2)								Hans-Gunther Moser	MPI Munich				
		%I0.1.8	EBOOL	CO2 OK (DSS3)								Hans-Gunther Moser	MPI Munich				
		%I0.1.9	EBOOL														
		%I0.1.10	EBOOL														
		%I0.1.11	EBOOL														
		%I0.1.12	EBOOL														
		%I0.1.13	EBOOL														
		%I0.1.14	EBOOL														
		%I0.1.15	EBOOL														
BMX DDI 1602	16-ch digital input	%I0.2.0	EBOOL	HumiditySniffer_1	%MW021							Benigno Gobbo	INFN Trieste				
slot 2		%I0.2.1	EBOOL	HumiditySniffer_2	%MW022							Benigno Gobbo	INFN Trieste				
		%I0.2.2	EBOOL	HumiditySniffer_3	%MW023							Benigno Gobbo	INFN Trieste				
		%I0.2.3	EBOOL	HumiditySniffer_4	%MW024							Benigno Gobbo	INFN Trieste				
		%I0.2.4	EBOOL	NTC_Temperature_1	%MW031							Pietro Cristaudo	INFN Trieste				
		%I0.2.5	EBOOL	NTC_Temperature_2	%MW032							Pietro Cristaudo	INFN Trieste				
		%I0.2.6	EBOOL	NTC_Temperature_3	%MW033							Pietro Cristaudo	INFN Trieste				
		%I0.2.7	EBOOL	NTC_Temperature_4	%MW034							Pietro Cristaudo	INFN Trieste				
		%I0.2.8	EBOOL	NTC_Temperature_5	%MW035							Pietro Cristaudo	INFN Trieste				
		%I0.2.9	EBOOL	NTC_Temperature_6	%MW036							Pietro Cristaudo	INFN Trieste				
		%I0.2.10	EBOOL	NTC_Temperature_7	%MW041							Pietro Cristaudo	INFN Trieste				
		%I0.2.11	EBOOL	NTC_Temperature_8	%MW042							Pietro Cristaudo	INFN Trieste				
		%I0.2.12	EBOOL	NTC_Temperature_9	%MW043							Pietro Cristaudo	INFN Trieste				
		%I0.2.13	EBOOL	NTC_Temperature_10	%MW044							Pietro Cristaudo	INFN Trieste				
		%I0.2.14	EBOOL	NTC_Temperature_11	%MW045							Pietro Cristaudo	INFN Trieste				
		%I0.2.15	EBOOL	NTC_Temperature_12	%MW046							Pietro Cristaudo	INFN Trieste				
BMX DDI 1602	16-ch digital input	%I0.3.0	EBOOL	WaterLeak_Disconnected_1	%MW051							Markus Friedl	Vienna				
slot 3		%I0.3.1	EBOOL	WaterLeak_Disconnected_2	%MW052							Markus Friedl	Vienna				
		%I0.3.2	EBOOL	WaterLeak_Disconnected_3	%MW053							Markus Friedl	Vienna				
		%I0.3.3	EBOOL	WaterLeak_Disconnected_4	%MW054							Markus Friedl	Vienna				
		%I0.3.4	EBOOL	WaterLeak_Disconnected_5	%MW055							Markus Friedl	Vienna				
		%I0.3.5	EBOOL	WaterLeak_Detected_1	%MW061							Markus Friedl	Vienna				
		%I0.3.6	EBOOL	WaterLeak_Detected_2	%MW062							Markus Friedl	Vienna				
		%I0.3.7	EBOOL	WaterLeak_Detected_3	%MW063							Markus Friedl	Vienna				
		%I0.3.8	EBOOL	WaterLeak_Detected_4	%MW064							Markus Friedl	Vienna				
		%I0.3.9	EBOOL	WaterLeak_Detected_5	%MW065							Markus Friedl	Vienna				
		%I0.3.10	EBOOL														
		%I0.3.11	EBOOL														
		%I0.3.12	EBOOL														
		%I0.3.13	EBOOL														
		%I0.3.14	EBOOL														
		%I0.3.15	EBOOL														
BMX DRA 0805	8-ch rele	%Q0.4.0	EBOOL	SVD_LV_Interlock_1	%MV101							BNC	Francesco Forti	INFN Pisa			
slot 4		%Q0.4.1	EBOOL	SVD_LV_Interlock_2	%MV102							BNC	Francesco Forti	INFN Pisa			
		%Q0.4.2	EBOOL	SVD_LV_Interlock_3	%MV103							BNC	Francesco Forti	INFN Pisa			
		%Q0.4.3	EBOOL	SVD_HV_Interlock_1	%MV111							BNC	Francesco Forti	INFN Pisa			
		%Q0.4.4	EBOOL	SVD_HV_Interlock_2	%MV112							BNC	Francesco Forti	INFN Pisa			
		%Q0.4.5	EBOOL	SVD_HV_Interlock_3	%MV113							BNC	Francesco Forti	INFN Pisa			
		%Q0.4.6	EBOOL	CO2_CoolingPlant_Interlock	%MV132								JC series 16 pin Female (4pin of 16)	Hans-Gunther Moser	MPI Munich		
		%Q0.4.7	EBOOL	WARM										Hans-Gunther Moser	MPI Munich		
BMX AMI 0410	4-ch analog inputs	%I0.5.0	INT	N2 Flow	%MW301	?								DESY ?			
slot 5		%I0.5.1	INT	DOCK_Chiller_flow	%MW302	?								D-SUB 9 pin male (2pin of 9)	Markus Friedler	Vienna	
		%I0.5.2	INT	Pressure	%MW303	?									?		
		%I0.5.3	INT														
BMX AMI 0410	4-ch analog inputs	%I0.6.0	INT														
slot 6		%I0.6.1	INT														
		%I0.6.2	INT														
		%I0.6.3	INT														
BMX DRA 0805	8-ch rele	%Q0.7.0	EBOOL	to Central Interlock SVD_LV_Int	%MV141										Sadaharo Uehara	KEK	
slot 7		%Q0.7.1	EBOOL	to Central Interlock SVD_HV_Int	%MV142										Sadaharo Uehara	KEK	
		%Q0.7.2	EBOOL	to Central Interlock PXD_Int	%MV143										Sadaharo Uehara	KEK	
		%Q0.7.3	EBOOL	to Central Interlock Waterleak_Int	%MV144										Sadaharo Uehara	KEK	
		%Q0.7.4	EBOOL	PXD_Interlock_1	%MV121										BNC	?	
		%Q0.7.5	EBOOL	PXD_Interlock_2	%MV122										BNC	?	
		%Q0.7.6	EBOOL	PXD_Interlock_3	%MV123										BNC	?	
		%Q0.7.7	EBOOL	DOCK_Chiller_Interlock	%MV131	?									D-SUB 9 pin male (2pin of 9)	Markus Friedler	Vienna

PLC I/O hardware completely defined:

- module types
- cables
- connectors


VLHI crate: CAD design

PLC crate internal cabling, I/O signal definitions and connection types:
all available in CAD drawings (here an example, PLC at top level)



VLHI crate: front view

Front view of the cabled PLC crate;
Two empty slots: analog modules (available) to be inserted



VLHI crate: top view

Top view of the PLC crate: interconnections cabled

