

CTA, with focus on LST

Masahiro Teshima

*ICRR, The University of Tokyo
Max-Planck-Institute for Physics*





cherenkov
telescope
array

CTA North at ORM

Observatorio del Roque de los Muchachos








cherenkov
telescope
array

CTA North Array Configurations

CTA Observatory consists of two sites, Chile
Paranal and Spain Canary Island to cover all sky.



LST 23m Low-Energy



MST 12m
Mid-Energy




cherenkov
telescope
array

Science with CTA

Energy frontier of Astrophysics




Origin of CR
UHECR




Cosmic Accelerators



Super Massive
Blackhole



Dark Matter



AGN




Gamma Ray Bursts



Supernova Rem.

Galactic Sources





Binaries

CTAN-LST Array

Sensitivity x3, Angular Resolution x2

Energy Range > 20GeV





- CTA-LST array contributes to the sensitivity in low energies
- >20GeV Threshold Energy
- Distant AGNs are observable up to z=2
- X10000 sensitivity for GRBs and AGN flares than Fermi
- First firm observation of GRBs from ground




cherenkov
telescope
array

GRBs: good targets for CTA-LSTs

Study the newborn baby black holes




CTA Simulation
(Template GRB080916C)






cherenkov
telescope
array


Toward the discovery of Dark Matter Complementarity with different approaches




thermal freeze-out (early Univ.)
indirect detection (now)



direct detection



production at colliders



- Explore Dark Matter in the Galactic Center and Dwarf Sph. Galaxies
- CTA has the best sensitivity above 700GeV


Steering Committee:

*DE: T. Schweizer
ES: M. Martinez (chair)
FR: J.-P. Lees*

JP: H. Kubo
IT: N. Giglietto
JAC: M. Vazquez Acosta

Ex Officio: M. Teshima
Ex Officio: J. Cortina
Ex Officio: D. Mazin

Version 7.10



CTA-LST Project : Big International Effort

BR(Brazil), CH(Switzerland), DE(Germany), ES(Spain), FR(France),
IN(India), IT(Italy), HR(Croatia), JP(Japan), SE(Sweden)

Focal Plane Instr.

Electronics (JP/IT/ES)

Camera body (ES)


Camera Supporting

Structure (FR/IT)

Flywheel, UPS (JP)

Computers, network (JP)

INFRA (ES)



Mirror (JP)

Interface Plate(DE/BR/JP)

Actuator (JP/CH)

CMOS-Cam (JP)

Star Guider (SE)

Calibration Box (IN/IT)

Structure (DE/ES)

Access Tower (DE/ES)

Drive (ES/FR)

Bogie (ES/DE/IT)

Rail (ES/DE)

Foundation (ES)



cherenkov
telescope
array

LST1 construction

Dish installed on the understructure, Dec 4, 2017





cherenkov
telescope
array

LST1 construction

Very good test for the ice load

No damage after ice storm Feb 6, 2018






cherenkov
telescope
array


CTA LST1 Construction Dummy CSS for balancing

Camera Supporting Structure
Dummy CSS, Counter Balance

Dummy CSS installed 17 Feb. 2018



Camera mechanics finished



Nov 2017

Status of LST1 construction

Backplanes of the camera installed

Jan 2018



IT computer center installed, 2k Cores, 3PB



Dec 2017

Power and Network ready

Mar 2018



Diesel

ATS, Transformer




500kW Flywheel Power Units



cherenkov
telescope
array

The LST-1 Site



on 11. May 2018





cherenkov
telescope
array

Camera Access Tower




198 Mirrors for LST1




198 Mirrors are brought to the LST1 site

The Radius of Curvature of mirrors
as a function of distance of the center



Preparation of Interface Plates and Actuators in MIRCA

Assembled Interface plates and Actuators



LST1 construction

Installing Mirror Interface Plates and actuators

3 March 2018



Mirror Installation




There is 'Martin' mirror as well ;)



cherenkov
telescope
array

Mirror installation is on-going



Camera Supporting Structure by LAPP/IN2P3

Camera support structure :

- production : finished
- Trial mounting : done in February
- Shipment : in progress
- Expected arrival date on site : 21 May





cherenkov
telescope
array

Camera Supporting Structure on the trailer





cherenkov
telescope
array

LST1 Status 2018.06.22


Camera Support Structure Arch




Modules for LST2-4+: PMTs



- 7-dynote 10000 PMTs delivered.
 - LST1 PMTs are with 8 dynodes.
- **QE peaked at 370 nm and >40%**
 - Slightly better than LST1
- HV at Gain 40k ranges 900 – 1200 V.
 - This diversity will be compensated by the attenuation in preamp.



5/15/18



7

Modules for LST2-4: Dragon boards



- 1100 Dragon boards delivered
- Difference w.r.t. 1st LSTs are
 - Sine wave injection circuit
 - Temperature and Humidity sensor
 - Voltage monitor
 - Other minor things
- 750 boards have a bad regulator. They are being replaced now.
- ~0.1% of DRS4 chips have also problems. They are being replaced.
- Big capacitor will be protected with an additional plastic piece




Camera Overview

Front Part




Camera dimensions:
2895x2895x1500 mm
Weight:
2077 kg



Camera Overview

Back Part



Camera Transport “CIEMAT”

Ciemat

Centro de Investigaciones
Energéticas, Medioambientales
y Tecnológicas




26th April





cherenkov
telescope
array


Integration and final test on-going at IFAE





cherenkov
telescope
array

CTA North IT System 2000 cores, 3PBytes



28 June 2018

Camera Access Tower




IT Container
2000 Core, 3PB





cherenkov
telescope
array

CTA-N INFRA in Phase 1



Phase 1 Schedule:

Detailed Design 2018 Q2-Q3
Start the Construction 2019 Q2
Telescope installation 2020 Q2



cherenkov
telescope
array

Time Schedule by CTAO

Project Phases



Current Phase




Financial
Threshold
Reached



LST 1 Prototype
Completed on
North Site

Summary

- **The construction of LST1 is going very smooth**
- **So far we did not see any major problem in the LST1 construction and also LST components**
- **We expect the first light in Sep 2018**
- **We appreciate the INFRA work for LST2-4 and MST3,15 is ongoing by PO and IAC**
- **October 10, 2018, Inauguration of LST1 is scheduled**



LST1 telescope construction site - Fri May 11 20:00:01 UTC 2018 - <http://www.lst1.iac.es>



cherenkov
telescope
array

Mounting of Camera support structure (CSS)

Mid June 2018

