Production tests and commissioning of the Pixel Vertex Detector for Belle II

Philipp Leitl phleitl@mpp.mpg.de

Max Planck Institute for Physics

2019-03-25




Max-Planck-Institut für Physik (Werner-Heisenberg-Institut)

From one module to an (almost) complete detector



PXD module test setup



From one module to an (almost) complete detector



"Mass testing"



- Focus on (fast) characterization of given modules.
- 65 modules had to be tested and optimized. This was done in a collaborative effort with colleagues from the Semiconductor Laboratory in Munich and from the Universities in Bonn and Göttingen.
- 49 modules were graded as class A.

Standardized Testing Procedure: Handbook



THE PXD MASS TESTING HANDBOOK

September 13, 2018 v0.7.1

handbook

- step by step instructions for the testing
- definition of software versions used
- mechanical instructions for module handling


Contents

1	Inst	callation	2	
	1.1	Test setup - Hardware	2	
	1.2	Test setup - Software	3	
	1.3	Software Preparations	4	
		1.3.1 host.ini, master.setup.ini and dheid	4	
		1.3.2 archiver	5	
		1.3.3 configuration commit	5	
	1.4	Mechanical Mounting	6	
	1.5	First Powerup	6	
2	Measurements 8			
	2.1	HS Link Scan	8	
	2.2	Delay Scan	9	
	2.3	Pedestals	9	
	2.4	Temperatures	10	
	2.5	Dead Pixel Map	10	
	2.6	Offsets 1	11	
	2.7	ADC curves	12	
	2.8	Offsets 2	13	
	2.9	Source scan	14	
	2.10	Discussion of the results	15	
3	Deir	nstallation	16	

The testing procedure of the main production modules is following the instructions of the handbook. Therefore, it is the same for each module and at each testing location.

What could possible go wrong when you glue?






Without words...





Matrix damages





The damaged matrix of W44_OF1 after gluing of ladder L2_024 is shown on the left side. The bright spot is the broken BCB passivation layer. The metal lines underneath were damaged as well resulting in short-circuits. The readout of the turned off matrix on the right side shows high current in the affected drains.


Less clear failures



power supply

It turned out that there was in addition a problem with the ramping procedure for the supply voltages which by chance worked or damaged modules.


Impacts in the matrices by hard dust particles (?)



The numbers of failures summed up and it was decided to stop the gluing process in order to not risk the loss of further good modules. Only layer 1 could be completed.

Ladder Overview - Diagram






Only the "mechanically" or "electrically broken" categories are directly correlated to the gluing process. Subtracting the modules, which broke during testing, the yield of the production gluing process was at 78%.

Phase 3 - half of the PXD detector




- only half of the planned PXD could be assembled
- 20 out of 40 modules are installed
- layer 1 is complete, only two layer 2 ladders



VXD - marriage of PXD and SVD






VXD - local cosmic ray test




- testing the DAQ
- collecting data for alignment
- gaining operation experience



VXD - local cosmic ray test



Charge integral per pixel for
7 hours of data taking



Reworked gluing procedure



Improvements

- modules are no longer flipped
- the sensitive area is not touched
- ceramic stiffeners are now placed from below

PXD2020



Outlook PXD2020